

4-031733

7-28

6 R

15-065-19017-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1957

NW NW SE /4 SEC. 17, 09 S, 23 W
2310 feet from S section line
2310 feet from E section line

E-10747 (Robinson #1)

Operator license# -

Lease Evergreen Project well # 1

Operator: Kansas State Fee Fund

County Graham

Address: Evergreen Project

Well total depth 3895 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 181 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 29 Month: July Year: 92

Plugging proposal received from: Carl Goodrow

Company: P.I.R.T. II Phone: 913-628-1200

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.
5 1/2" circ. with black magic bottom cement NA.
Hole open to bottom.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 6:00P.M., Day: 28, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 181' cwc. 5 1/2" set @ 3895'.
Perf. NA. Shots @ 1900' and 1100'. Recovered 461' of 5 1/2" casing.
Ran tubing to 1800'. Circulated cement. Laid down tubing.
Squeezed 8 5/8" with 300 sx. with 500# hulls. Mixed in to Max. P.S.I.
300#. Close in P.S.I. 300#. Plug complete.

Remarks: Anhy. 1900'. Kiowa 1100'.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation:

I did[X] / did not[] observe the plugging.

Carl Goodrow

(agent)

STATE CORPORATION COMMISSION
RECEIVED
AUG 10 1992
CONSERVATION DIVISION
Wichita, Kansas
GL