

7-29

5 R

4- 031731

15-065-02829-0001

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1958

S2 NE NW /4 SEC. 17, 09 S, 23 W
4290 feet from S section line
3000 feet from E section line

E10747 (Robinson A #13)

Lease Evergreen Project well # 13

Operator license# -

Operator: Kansas State Fee Fund

County Graham

Address: Evergreen Project

Well total depth 3845 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well , Gas well , ^{ENHR} Input well X, SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: Day: 29 Month: July Year: 92

Plugging proposal received from: Carl Goodrow

Company: P.I.R.T. II Phone: 913-628-1200

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.
5 1/2" circ. with black magic bottom cement NA.
Hole open to bottom.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00AM., Day: 29, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 219' cwc. 5 1/2" set @ 3845'.
Perf. 3783' - 3825'. Shots @ 1900' and 1100'.

Recovered 575' of 5 1/2" casing. Ran tubing to 1800'. Circulated
cement. Laid down tubing. Squeezed 8 5/8" with 240 sx. cement blend
with 500# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 300#.
Plug complete.

Remarks: Anhy. 1900'. Kiowa 1100'.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X NO

Plugged through TUBING , CASING X. Elevation:

I did[X] / did not[] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
8-10-92
AUG 10 1992
CONSERVATION DIVISION
Wichita, Kansas

HD