

4-031729

7-28

7R

15-065-02825-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1957

NW SE NE /4 SEC. 17, 09 S, 23 W
3630 feet from S section line
990 feet from E section line

(Robinson A #7)

Operator license# -

Lease Evergreen Project well # 7

Operator: Kansas State Fee Fund

County Graham

Address: Evergreen Project

Well total depth 3916 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 215 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 28 Month: July Year: 92

Plugging proposal received from: Carl Goodrow

Company: P.I.R.T. II Phone: 913-628-1200

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.
5 1/2" circ. with black magic bottom cement NA.
Hole open to bottom.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 28, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 215' cwc. 5 1/2" set @ 3918'.
Perf. 3854' - 3858'. P.B.T.D. 3880'. Shots @ 1900' and 1100'.
Recovered 582' of 5 1/2" casing. Ran tubing to 1800'. Circulated
cement. Laid down tubing. Squeezed 8 5/8" with 225 sx. cement blend
with 500# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 400#.
Plug complete.

Remarks: Anhy. 1900'. Kiowa 1100'.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Carl Goodrow

(agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1992
CONSERVATION DIVISION
Wichita, Kansas