

4- 031730

7-28

SR

15-065-02826-0000

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1957

SE NW NE /4 SEC. 17, 09 S, 23 W  
4290 feet from S section line  
1650 feet from E section line

Operator license# -

Lease Evergreen Project well # 8

Operator: Kansas State Fee Fund

County Graham

Address: Evergreen Project

Well total depth 3945 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 28 Month: July Year: 92

Plugging proposal received from: Carl Goodrow

Company: P.I.R.T. II Phone: 913-628-1200

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
5 1/2" circ. with black magic bottom cement NA.  
Hole open to bottom.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:00A.M., Day: 28, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 218' cwc. 5 1/2" set @ 3945'.  
Perf. 3867' - 3873'. P.B.T.D. 3895'. Shots @ 1900' and 1100'.  
Recovered 534' of 5 1/2" casing. Ran tubing to 1800'. Circulated  
cement. Laid down tubing. Squeezed 8 5/8" with 300 sx. cement blend  
with 500# hulls mixed in to Max. P.S.I. 300#. Close in P.S.I. 300#.  
Plug complete.

Remarks: Anhy. 1900'. Kiowa 1100'.

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES     NO    

Plugged through TUBING    , CASING X. Elevation:    

I did[ X ] / did not[     ] observe the plugging. Carl Goodrow

10

(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
8-10-92  
AUG 10 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS