

CONFIDENTIAL

Operator Name: M & M Exploration, Inc. Lease Name: Davis Ranch OWWO Well #: B-1
Sec. 15 Twp. 34 S. R. 15 East West County: Barber

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No Log Formation (Top), Depth and Datum Sample

Samples Sent to Geological Survey Yes No Name Top Datum

Cores Taken Yes No Penn 3120 -1428

Electric Log Run Yes No Heebner Shale 4034 -2342

List All E. Logs Run: Cherokee Shale 4838 -3146

Array Induction, Density/Neutron Mississippi 4870 -3178

KCC OCT 05 2005 CONFIDENTIAL

Table with 8 columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Rows include Conductor, Surface, and Production.

Table with 5 columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives. Includes 'RECEIVED OCT 11 2005 KCC WICHITA' stamp.

Table with 4 columns: Shots Per Foot, PERFORATION RECORD - Bridge Plugs Set/Type, Acid, Fracture, Shot, Cement Squeeze Record, Depth. Rows 1 and 2.

TUBING RECORD Size 2 3/8" Set At 4931' Packer At Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil Bbls. 5 Gas Mcf 400 Water Bbls. 120 Gas-Oil Ratio 80,000 Gravity

Disposition of Gas METHOD OF COMPLETION Production Interval Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled 4866-4926 OA

ALLIED CEMENTING CO., INC. 20865

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <i>7-3-05</i>	SEC. <i>15</i>	TWP. <i>34S</i>	RANGE <i>15W</i>	CALLED OUT <i>4:00 AM</i>	ON LOCATION <i>6:15 AM</i>	JOB START <i>11:55 AM</i>	JOB FINISH <i>12:35 PM</i>
LEASE <i>Davis Ranch</i>	WELL # <i>B-1</i>	LOCATION <i>Deerhead Ks. South to Cottage Creek Road 1 1/4 E, S/S</i>			COUNTY <i>Barber</i>	STATE <i>Ks.</i>	
OLD OR NEW (Circle one) <u>NEW</u>							

CONTRACTOR *Duke #7*

TYPE OF JOB *Production*

HOLE SIZE *7 7/8* T.D. *5165'*

CASING SIZE *4 1/2 x 10.5"* DEPTH *4958'*

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX *1600* MINIMUM _____

MEAS. LINE _____ SHOE JOINT *10'*

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT *79 3/4 Bbls 2% KCL*

EQUIPMENT

PUMP TRUCK # *343* CEMENTER *Carl Belding*

BULK TRUCK # *356* DRIVER *Terry Gould*

CEMENTER HELPER *Dennis Cushmanberg*

DRIVER _____

OWNER *M+M Exploration*

CEMENT *8 Bals Clapro*

AMOUNT ORDERED *25 sx 60:40:6*

150 sx Class H 10% Gyp-seal 10% salt

8" Rot-seal .8% FT-160 500 gal mud-clean

COMMON <i>H</i>	<i>150 sx</i>	@	<i>10.50</i>	<i>1575.00</i>
POZMIX	<i>10 sx</i>	@	<i>4.70</i>	<i>47.00</i>
GEL	<i>2 sx</i>	@	<i>14.00</i>	<i>28.00</i>
CHLORIDE		@		
ASC		@		
<i>Class A</i>	<i>15 sx</i>	@	<i>8.70</i>	<i>130.50</i>
<i>Gyp-seal</i>	<i>14 sx</i>	@	<i>19.15</i>	<i>268.10</i>
<i>Salt</i>	<i>16 sx</i>	@	<i>7.90</i>	<i>126.40</i>
<i>Rot-seal</i>	<i>1200 #</i>	@	<i>.60</i>	<i>720.00</i>
<i>FT-160</i>	<i>113 #</i>	@	<i>8.70</i>	<i>983.10</i>
<i>Mud-clean</i>	<i>500 Gals</i>	@	<i>1.00</i>	<i>500.00</i>
<i>Clapro</i>	<i>8 Bals</i>	@	<i>22.90</i>	<i>183.20</i>
		@		
HANDLING	<i>233</i>	@	<i>1.60</i>	<i>372.80</i>
MILEAGE	<i>45 / .06 / 233 sx</i>			<i>629.10</i>
				TOTAL <i>5563.20</i>

REMARKS:

Run 4958' csg Break circulation 15 min. Drop ball for shoe, circulate + open tool -1000 psi circulate for 30 minutes start mud-clean plug rat + mouse hole w/ 25 sx 60:40:6. Mix + pump 150 sx Class H + additives wash pump + lines Release plug dip w/ 79 3/4 Bals sand plug + float held

SERVICE

DEPTH OF JOB	<i>4958'</i>		
PUMP TRUCK CHARGE			<i>1435.00</i>
EXTRA FOOTAGE		@	
MILEAGE	<i>45</i>	@	<i>5.00 225.00</i>
MANIFOLD		@	
<i>Head Pentac</i>		@	<i>75.00</i>
RECEIVED			

OCT 11 2005

KCC WICHITA

TOTAL *1735.00*

CHARGE TO: *M+M Exploration*

STREET _____

CITY _____ STATE _____ ZIP _____

4 1/2" PLUG & FLOAT EQUIPMENT

<i>1- Tri Plex shoe</i>	@	<i>1300.00</i>	<i>1300.00</i>
<i>1- Latch Down plug</i>	@	<i>300.00</i>	<i>300.00</i>
<i>1- Basket</i>	@	<i>116.00</i>	<i>116.00</i>
<i>4- Centralizers</i>	@	<i>45.00</i>	<i>180.00</i>
<i>1- 4 1/2 x 10' L-T</i>	@	<i>13.50</i>	<i>135.00</i>
TOTAL <i>2031.00</i>			

To Allied Cementing Co., Inc.:-
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE *Alan Vratil*

TAX _____

TOTAL CHARGE ~~*2031.00*~~

DISCOUNT ~~_____~~ IF PAID IN 30 DAYS

PRINTED NAME *Alan Vratil*