



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

15-065 - 03058-00-00

DEC 28 1964
12-28-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co has this

date requested permission to plug the following described well:

Imperial Oil of Kans. Inc.,
Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company of Kansas, Incorporated,

Complete Address: 2318 Washington, Great Bend, Kansas.

Lease Name: Rice Well No. 1

Location: NE-SW-SE Sec. 4 Twp. 10 Rge. 8 (E) (W) 23

County Graham Total Depth 4241 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

190' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.
4240' -- 5 1/2" Production casing cemented with 125 Sx. Well Plugged
back to 4165'. Top perforations from 3822' to 3826'.

Sand well back to 3800' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud, Pull 5 1/2" to 540'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 180' and dis-
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and
10 Sx. cement to bottom of cellar.

Very truly yours,

H. A. Dickel
Conservation Division Agent