

State of Kansas



15-163-20164-0000

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mason of Dunne-Gardner has this

date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza Wichita, Ks.

Lease Name: Baumgarten Well No. 1

Location: NW NW SW Sec. 25 Twp. 9 Rge. 19 (E)(W) X

County: Rooks Total Depth 3670 Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Mason was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Leo F. Masser  
Conservation Division Agent