

RECEIVED

AUG 07 2003

KCC WICHITA

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 S. Market, Room 2018  
Wichita, KS 67202

FORM CP-1  
Rev. 03/92

~~15-163-90357-00-00~~

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM AND FILE ONE COPY)

15-163 03051-00-01

API # 06/03/49 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API # was issued. Indicate spud or completion date.

WELL OPERATOR Corsair Energy, LC KCC LICENSE # 5058  
(owner/company name) (operator's)

Address 914 E Douglas Ave CITY Wichita

STATE Kansas ZIP CODE 67202 PHONE # (316) 267-7779

LEASE Benoit B SWD WELL # #1 SEC 25 T. 9S R. 19W

	NW	NW	NW
--	----	----	----

 SPOT LOCATION /QQQQ COUNTY Rooks, KS

4950 FSL FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4959 FEL FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D&A \_\_\_\_\_ SWD/ENHR X DOCKET# D02917

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 265 CEMENTED WITH 125 SACKS

PRODUCTION CASING SIZE 5 1/2' SET AT 3564 CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGE PLUG SETS:

ELEVATION 2148 T. D. 3569 PBDT 3564 ANHYDRITE DEPTH 1773

(GL/KB)

(STONE CORRAL)

CONDITION OF WELL: GOOD POOR X CASING LEAK \_\_\_\_\_ JUNK IN HOLE X

PROPOSED METHOD OF PLUGGING Perforate @ 900' squeeze 50 -100 sx 60/60 poz w/ 10% gel, 1/4# flocele load casing with cement after squeeze, 200 sx, dig out cellar plug w/ 50 sk. Per Dennis Hamel 8/5/03

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? \_\_\_\_\_

If not explain why? No logs run in well

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K. S. A. 55-101 et. Seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jim Collins PHONE# (316) 267-7779

ADDRESS 914 E. Douglas Ave City/State Wichita, KS 67202


PLUGGING CONTRACTOR Plains, Inc. KCC LICENSE# 4072  
(company name) (contractor's)

ADDRESS Box 346, Ness City, KS 67560 PHONE# (785) 798-3995

PROPOSED DATE AND HOUR OF PLUGGING (If known?) 8/05/03 2:00PM

PAYMENT OF THE PLUGGING FEE (K.A.R.) 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/5/2003 AUTHORIZED OPERATOR/AGENT

*Plugged*  
  
(signature)

11/03