

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-925-20728 -00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date September 1985

Well Operator: Murfin Drilling Company, Inc. KCC License #: 30606  
(Owner / Company Name) (Operator's)

Address: 250 N. Water, Suite 300 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: (316) 267-3241

Lease: Pyle Well #: 1-12 Sec. 12 Twp. 33 S. R. 26 ☐ East ☒ West

E/2 - NE - SE Spot Location / QQQQ County: Meade

2060 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☐ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well

☒ SWD Docket # D26729 ☐ ENHR Docket #                      ☐ Other:                     

Conductor Casing Size:                      Set at:                      Cemented with:                      Sacks

Surface Casing Size: 8 5/8 Set at: 1262 Cemented with: 660 Sacks

Production Casing Size: 5 1/2 Set at: 5336 Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: Marmaton 5125-5128; CIBP 3520; Wabaunsee 3389-3394; Admire 3214-3220, 3256-3260, 3272-3282, 3320-3324.

Elevation: 2226 (☐ G.L. / ☒ K.B.) T.D.: 7125 P.B.T.D.: 3457 Anhydrite Depth:                       
(Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): CIBP @ 3200 w/2 sxs cmt; Pull ±3000' 5-1/2" csg.

Proposed plugs: 1330' 15 sxs gel, 50 sxs 60/40 poz cmt plg; 750' 50 sxs cmt plg; 300' 50 sxs cmt plg; 40' 10 sxs cmt plg.

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 07 2008

Is Well Log attached to this application as required? ☐ Yes ☒ No Is ACO-1 filed? ☒ Yes ☐ No

If not explain why? Filed with ACO-1.

CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Stan Froetschner

Production Superintendent                      Phone: (785) 483-1197

Address: P.O. Box 288 City / State: Russell, KS 67665

Plugging Contractor: Mike's Testing & Salvage Inc. KCC License #: 31529  
(Company Name) (Contractor's)

Address: P.O. Box 467; Chase, KS 67524 Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): October 2008 - Please call Rich Pancake for questions.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/03/08 Authorized Operator / Agent: Ronald A. Schwarden  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

MURFIN DRILLING CO., INC.  
250 N WATER STE 300  
WICHITA, KS 67202-1216

October 13, 2008

Re: PYLE #1-12  
API 15-119-20728-00-01  
12-33S-26W, 2060 FSL 330 FEL  
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after April 11, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888