

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,797-0000

LEASE NAME Flora

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #18-5

2970 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR L.B. Petroleum, Inc.

SEC. 18 TWP. 10S RGE. 26 ~~W~~ (W)

ADDRESS 370 17th Street Suite #3200
Denver, Colorado 80202

COUNTY Sheridan

PHONE# (303) 629-1447 OPERATORS LICENSE NO. _____

Date Well Completed 1-24-85

Character of Well D. & A

Plugging Commenced 1-24-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-24-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	8 5/8" 7 jts.	new	24#	295' cut	some of	E, total 289' set @ 286'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged @ 4500' w/180 sx. 50-50 posmix, 3% c.c., 6% gel, 1 sx. of celloflake, 1 sx. hulls, 1 - 8 5/8" plug, 1st plug @ 2260' w/20 sx. 2nd plug @ 1360' w/100 sx., 3rd plug @ 330' w/40 sx., solid bridge @ 40' w/10 sx. 10 sx. in the rat hole David Wann District #6
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. License No. 5883

Address 905 Century Plaza

Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

F.W. Shelton, Jr., (Employee of Operator) ~~Operator~~ of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F.W. Shelton, Jr.

(Address) F.W. Shelton, Jr., Vice Pres.

905 Century Plaza Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 24 day of Jan., 19 85



Martha E. Gustin
Martha E. Gustin Notary Public

Commission Expires: 4-15-85