

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sheridan SEC. 20 TWP. 10S RGE. 26 X E/W
Location as in quarters or footage from lines:

NW SW NW

Lease Owner Houston Hyrolance International
 Lease Name Werth Well No. #1
 Office Address P.O. Box 3723, Victoria, Tx. 77903
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 10-23-83
 Application for plugging filed 10-23-83
 Plugging commenced 10-23-83
 Plugging completed 10-23-83
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation _____ Depth to top _____ bottom T.D. 4165'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	387'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Spotted 20 sx. cement @ 2210' thru drill pipe.
- Spotted 100 sx. cement @ 1320' thru drill pipe.
- Spotted 40 sx. cement @ 420' thru drill pipe.
- Set bridge plug, Spotted 10 sx. cement @ 40' thru drill pipe.
- Spotted 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita
(Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1983




David F. Jamis
David F. Jamis, Notary Public.

My Commission expires _____

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1983

CONSERVATION DIVISION
Wichita, Kansas



15-179-20706-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Houston Hydrolance International P.O. Box 3723 Victoria, Tx. 77903

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Werth Well No. #1

Sec. 20 T. 10S R. 26W Spot NW SW NW

County Sheridan State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 387' with 250 sx. 2%gel
3%cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4165'

Drilling Commenced 10-12-83 Drilling Completed 10-23-83

Formation	From	To	Tops
Cellar	0	7	Anhydrite 2203
Sod	7	30	
Shale	30	95	
Sand, Shale	95	1140	
Shale, Lime	1140	1891	
Sand	1891	1990	
Shale, Sand	1990	2203	
Lime, Shale	2203	2840	
Lime	2840	3255	
Shale, Lime	3255	3375	
Lime	3375	3535	
Shale, Lime	3535	3715	
Lime, Shale	3715	3850	
Lime	3850	3895	
Lime, Shale	3895	3980	
Lime	3980	4165	

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1983
CONSERVATION DIVISION
Wichita, Kansas