


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 21 Twp. 10S Rge. 26W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE 1/4 NE 1/4 NE 1/4
Lease Owner: Leben Drilling, Inc.
Lease Name: Phelps Well No. 1
Office Address: 905 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-20-58 19
Application for plugging filed 2-20-58 19
Application for plugging approved 2-20-58 19
Plugging commenced 2-20-58 19
Plugging completed 2-20-58 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Frabicius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	231'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 550' w/25 sacks cement
2nd plug @ 240' w/15 sacks cement
top plug @ 40' w/10 sacks cement & 1/2 sacks hulls
to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
2-26-58
FEB 26 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Frank Hamlin (employee of owner) or ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 19 58

My commission expires June 17, 1961
Ruth N. Benjamin Notary Public.

PLUGGING
FILE SEC 21 T 10 R 26 W
BOOK PAGE 85 LINE 14

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

LEBEN DRILLING, INC.
LEBEN DRILLING, INC.
PHELPS #1
NE1/4 NE1/4 NE1/4 sec. 21-10S-26W
SHERIDAN COUNTY, KANSAS
2-7-58
2-20-58

COMMENCED:
COMPLETED:

0	75	Shale & Sand	
75	125	Post Rock Sand	
125	232	Blue Shale	
232	310	Shale & Sand	TOPS:
310	1475	Sand & Shale	
1475	1595	Shale	ANHYDRITE 2205
1595	1810	Lime & Shale	TOPEKA 3537
1810	1970	Shale & Sand	HEEBNER 3913
1970	2205	Red Bed & Shale	TORONTO 3834
2205	2242	Anhydrite	LANS.-K.C. 3354
2242	2510	Shale & Lime	BS, K.C. 4093
2510	2595	Lime & Shale	
2595	2960	Shale & Lime	ELEVATION 2576 R.B.
2960	3230	Lime & Shale	
3230	3625	Shale & Lime	
3625	3854	Shale & Lime	
3854	3963	Lime-Lans.-K.C.	
3963	3950	Lime	
3950	3990	Lime & Shale	
3990	4093	Lime	
4093	4115	Shale & Lime	
4115	4115	Rotary Total Depth	

Set 231' of a 5/8" surface casing with 150 sacks cement and 3% CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Phelps #1, located NE1/4 NE1/4 NE1/4 of Section 21, Township 10 South, Range 26 West, Sheridan County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By:

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK)SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of February, 1958.

Butt N. Benjamin
Butt N. Benjamin, Notary Public

My Commission Expires:
June 17, 1961.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 4/T. 10 R. 26W
BOOK PAGE 25 LINE 19