

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-21,064-0006

LEASE NAME Rhoades

WELL NUMBER #1

1320 Ft. from S Section Line

1980' Ft. from E Section Line

SEC. 22 TWP. 10S RGE. 26 (E) or (W)

COUNTY Sheridan

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-8-93

Plugging Completed 8-8-93

TYPE OR PRINT.  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-8-93 (date)

by Herb Dines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put in  | Pulled out |
|-----------|---------|------|----|--------|---------|------------|
|           |         |      |    | 8 5/8" | 228.70' | None       |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set  
Fill w/heavy mud; set 1st plug @ 2225'-2125' w/25 sx; 2nd plug @ 1300'-900' w/100 sx; 3rd plug @ 280'-120' w/40 sx; 4th plug @ 40'-surface w/10 sx; rathole 15 sx; Total 190 sx; 60-40 posmix 6% gel 1/2# Floseal per sx.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 3068

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

ANGELA WOODARD  
Notary Public • State of Kansas  
My Appt. Expires \_\_\_\_\_

(Signature) Jack K. Wharton

(Address) 150 N. Main, Ste 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 93

Angela Woodard  
Notary Public

My Commission Expires: March 20, 1997

USE ONLY ONE SIDE OF EACH FORM

RECEIVED  
OCT 15 1993  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas