


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sheridan County, Sec. 16 Twp. 10 Rge. 27 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Aurora Gasoline & Woodman & Iannitti Drilling Co.
Lease Name Schoenfeld Well No. 1
Office Address 717 Union National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-30 1958
Application for plugging filed 1-30 1958
Application for plugging approved 1-30 1958
Plugging commenced 1-30 1958
Plugging completed 1-30 1958
Reason for abandonment of well or producing formation Dry.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4103 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	164	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud. Bottom plug at 500' with 25 sacks cement.
Next plug at 175' with 15 sacks cement. Top plug at 40' with 10 sacks cement.

RECEIVED
STAT. CORPORATION COMMISSION
2-4-58
FEB 4 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Woodman & Iannitti Drilling Company
Address P. O. Box 387, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. T. Woodman (employee of owner) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
K. T. Woodman
717 Union Nat'l. Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of February, 1958

Mildred E. Lick
Mildred E. Lick, Notary Public.



PLUGGING
FILE SEC 16 T. 10 R. 27W
BOOK PAGE 80 LINE 27

D R I L L I N G L O G

Company: Aurora Gasoline & Woodman & Iannitti Drilling Co.
 Lease: #1 Schoenfeld - SW SW NE - 16-10-27W
 Sheridan County
 Contractor: Woodman & Iannitti Drilling Company
 P. O. Box 387, Hoisington, Kansas
 Date Commenced: 1-20-58
 Date Completed: 1-30-58
 Total Depth: 4103'
 Casing: 8 5/8" at 164 with 100 sacks cement

KB: 2655

Figures Indicate the Bottom of Formation

0-140	Sand	3125	Broken Lime
164	Shale	3275	Lime
220	Blue Shale	3406	Lime
285	Sandy Shale	3515	Lime & Shale
1605	Shale - Sand	4103	Total Depth
1764	Shale - Shells		
1800	Shale - Shells		
2060	Shale, Shells & Redbed		
2260	Redbed - Shale		
2285	Anhydrite		
2300	Lime - Shale		
2490	Shale - Shells		
2750	Shale - Lime		
2770	Broken Sandy Lime		
2890	Broken Lime		
2990	Lime		

GEOLOGICAL TOPS

Anhydrite	2260
Heebner	3812
Toronto	3834
Lansing	3850
B/KC	4089
Total Depth	4103

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
 K. T. Woodman

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING	
FILE SEC	16 T. 10 R. 27W
BOOK PAGE	80 LINE 27