

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-179-20888-00-00

LEASE NAME Park College

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S. Section Line

990 Ft. from E Section Line

SEC. 14 TWP. 10 RGE. 27 (E) or (W)

COUNTY Sheridan

Date Well Completed 2/5/87

Plugging Commenced 2/5/87

Plugging Completed 2/6/87

LEASE OPERATOR Mid-Continent Energy Corp.

ADDRESS 120 S. Market Suite 310 Wichita

PHONE#(316) 265-9501 OPERATORS LICENSE NO. 5205

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays Field office

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation none Depth to Top _____ Bottom T.D. 3880

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From	To	Size	Put in	Pulled out
	water	0	333	8 5/8	333	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1 @ 2210 w/20 sx; 2@ 1290 w/ 100 sx & 1 sk celloflake; 3@ 385 w/ 40 sx
4 @ 40' w/ Wiper plug & 10 sx; 10 sx rat hole & 10 sx mouse hole

190 sx total 60/40 poz 6% gel Job complete 9:30 am 2/5/87 (Ed Schumacher)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV Drilling License No. 5651

Address Box 905 McPherson Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kent R. Roberts

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Kent R. Roberts

(Address) 120 S. Market #310 Wichita

SUBSCRIBED AND SWORN TO before me this 13 day of February, 1987

Monak Stein
Notary Public

My Commission Expires:



Received
2-13-87