


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sheridan County. Sec. 7 Twp. 10S Rge. (E)/28 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name LINDENMAN Well No. 1  
Office Address 801 Union Center; Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 17, 19 69  
Application for plugging filed (verbally) April 16, 19 69  
Application for plugging approved " April 16, 19 69  
Plugging commenced April 16, 19 69  
Plugging completed April 17, 19 69  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4181 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	272'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 1250' w/65 sx. cement;  
Set 2nd plug @ 300' w/15 sx. cement;  
Set 3rd plug @ 40' w/ 5 sx. cement;  
Put 3 sx. cement in the rat hole.  
Job completed at 12:00 a.m., 4-17-69.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address (office) 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
A. L. Abercrombie (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
A. L. Abercrombie  
801 Union Center; Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 18th day of April, 1969.

My commission expires July 15, 1972  
Sue J. Blunck  
Sue J. Blunck, Notary Public.



CONTRACTOR'S WELL LOG

OWNER: Abercrombie Drilling, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Lindenman #1  
 LOCATION: NE NE NW, Sec. 7-10S-28W  
 Sheridan County, Kansas  
 GEOLOGIST: Jack K. Wharton  
 SPUD DATE: April 10, 1969  
 COMPLETION DATE: April 17, 1969

0	85	Clay
85	130	Sand
130	1290	Shale
1290	1830	Shale & Sand
1830	2046	Shale, Gyp & Sand
2046	2179	Sand
2179	2392	Red Shale
2392	2426	Anhydrite
2426	2800	Shale
2800	3205	Shale & Lime
3205	3315	Lime & Shale
3315	3391	Lime
3391	3637	Lime & Shale
3637	4181	Lime
	4181	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 22 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

FORMATION SAMPLE	TOPS	ELEVATION
Top/Anhydrite	(+ 392) 2392	2784 K. B.
Howard	(- 803) 3587	2782 D. F.
Topeka	(- 891) 3675	2776 G. L.
Heebner	(-1108) 3892	
Toronto	(-1137) 3921	
Lansing	(-1146) 3930	
B/K. C.	(-1396) 4180	

Drilled 280' of 9" surface hole and set 7", 23# csg., @272' w/135 sx. Sunset cement. Cement circulated. Plug was down 5:15 p.m., 4-10-69. Dry & Abandoned.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

A. L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Lindenman #1, NE NE NW, Sec. 7-10S-28W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: A. L. Abercrombie  
 A. L. Abercrombie  
 President

Sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, as of this 18th day of April, 1969.

Sue J. Blunck  
 Sue J. Blunck, Notary Public

My Commission Expires:

July 15, 1972