

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20152-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 1 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 11-1-1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. George Galloway of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Galloway guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling, Inc., & Zenith Drlg. Corp., Inc.

Complete Address: 1620 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Koerber Well No. 1-24

Location: 2200' FSL & 2200' FEL Sec. 24 Twp. 10 Rge. (E)(W) 29

County: Sheridan Total Depth 4190' ~~4132'~~ Oil Well.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Galloway was instructed to plug the well as follows:

280'--8 5/8" Surface casing, cement circulated.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx. cement thru DP. Pull DP to 280' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent