



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1974
03-11-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20374-00-00

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company, Incorporated,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Hecht Well No. 1

Location: CNW-SE Sec. 15 Twp. 10 Rge. (E)(W) 30

County: Sheridan Total Depth 4570 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

298'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1275'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent