



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Ambuster of Pioneer Drilling Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises Inc.

Complete Address: 308 West Mill - Pawnee, Kans 67663

Lease Name: Bartlett Well No. #1

Location: SE - NW - SW Sec. 25 Twp. 9<sup>S</sup> Rge. 19 (W)

County: Rooks Total Depth: 3690<sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Ambuster was instructed to plug the well as follows:

- 8 5/8" 206<sup>FE</sup> SP. Cur w/
- Driller 110<sup>SE</sup> 50/50 Permox 6% Gel. + 8 5/8" Plug - Elev. 2193<sup>SE</sup>
- spot with Drill Stem - with heavy mud between all plugs
- 1<sup>st</sup> Plug @ 780<sup>FE</sup> w/ 70<sup>SE</sup> Cmt.
- 2<sup>nd</sup> Plug @ 180<sup>FE</sup> w/ 25<sup>SE</sup> Cmt.
- 3<sup>rd</sup> Plug - solid bridge @ 40<sup>FE</sup> to 0<sup>in</sup> / 110<sup>SE</sup> Cmt.

Very truly yours, (By allied Cmt)

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 3 1980

CONSERVATION DIVISION  
Wichita, Kansas

Marion Schmidt  
Conservation Division Agent