



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1971
CONSERVATION DIVISION
Wichita, Kansas
02-05-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193 - 20035-00-00

Dear Sir:

Mr. Earl Baker of National Co-op Refnry Assn., has this date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association,

Complete Address: Box #6, Great Bend, Kansas.

Lease Name: Huelsmann Well No. 1

Location: CNE-NE Sec. 20 Twp. 10 Rge. (E)(W) 32

County: Thomas Total Depth 4710 Oil-Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Baker was instructed to plug the well as follows:

283'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1500'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

R. L. Nichols
Conservation Division Agent