

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1969

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Hinderliter of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Co., Inc.

Complete Address: 435 Page Court, Wichita, Ks. 67202

Lease Name: Shaffer "A" Well No. 1

Location: 2310'fn1 & 990'Fw1 SE SW NW Sec. 18 Twp. 11 Rge. 13 (E) (W)

County: Russell Total Depth: 3750'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Hinderliter was instructed to plug the well as follows:

8 5/8"-235' S.P. cuc. w/135 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 230' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

Conservation Division Agent