

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 4-21-1964
 APR 21 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. P. E. Plouffe of Blackstone Drilling, Inc has this date requested permission to plug the following described well:

Mr. Don McKellar guarantees payment of the plugging fee.

Operator's full Name: Don McKellar Oil Explorations

Complete Address: Box 173, Salina, Kansas

Lease Name: Crawford Well No. # 1

Location: 6 NW SE Sec. 21 Twp. 11 Rge. 13 (E) (W) W

County Russell Total Depth 3253 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. P. E. Plouffe was instructed to plug the well as follows:

8 5/8" 277' Gwc.

Filled hole with heavy mud to 270'; set plug with 1/4
sax hulls; displaced 25 sax cement thru drill pipe. Mud
to 40'; 1/2 sax hulls; rock bridge & displaced 10 sax
cement, cementing to base of cellar.

Very truly yours,

Don McKellar
 Conservation Division Agent