

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Hinderliter of Rains & Williamson Oil Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Co., Inc.

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name: Trapp Trust Well No. #1

Location: SW/NE/SW Sec. 32 Twp. 11, Rge. 13 (E) (W)

County: Russell Total Depth: 3690'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Larry Hinderliter was instructed to plug the well as follows:

8 5/8"-245' sp. cuc. with 165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug. Spotted with drill stem-with heavy mud between all plugs.

- 1st plug @ 660' w/70 sacks cement
- 2nd plug @ 240' w/40 sacks cement
- 3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement.
- 5 sacks of cement in rat hole.

Very truly yours,

Gilbert R. Schenk
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
9-28-1981
SEP 28 1981
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-30-81
INV. NO. 8206-W