



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Lue Burcher of Rains & Williamson Oil Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Co. Inc.

Complete Address: 435 Page Court 220W, Douglas, Wichita, Ks. 67202

Lease Name: Acker Well No. 1

Location: NW SW NW Sec. 14 Twp. 11 Rge. 14 (E) (W)

County: Russell Total Depth: 3705'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Burcher was instructed to plug the well as follows:

8 5/8" - 243' S.P. cas. w/185 sacks Common - 2% Sul. - 3% Cal. Cl.
Ordered 160 sacks 50% pozmix - 4% Sul. - 3% Cal. Cl. & 8 5/8" plug. Spot w/drill
stem w/ heavy mud between all plugs. 1st plug C 600' w/100 sacks cement
2nd plug C 250' w/40 sacks cement, 3rd plug - solid bridge of balls & plug C
40' w/10 sacks. Circulate 10 sacks in rat hole.

Very truly yours,

Keith R. Schel
Conservation Division Agent