

15-167-21914-00-00

FORM CP-2

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ben Griffin of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: Corie Oil Operations

Complete Address: R. R. #1, Box 83, Russell, Kansas 67665

Lease Name: Scott Well No. #1

Location: NW NW SE Sec. 22 Twp. 11 Rge. 14W (E) (W)

County: Russell Total Depth: 3319'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Griffin was instructed to plug the well as follows:

8 5/8"-253' s.p. cuc. w/160 commoh-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 260' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.

Circulate 10 sacks of cement in rat hole.

Very truly yours,

Conservation Division Agent

MAY 24 1984
5-24-1984
CONSERVATION DIVISION
Wichita, Kansas