

JUN 12 2008

WELL COMPLETION FORM

ORIGINAL

WELL HISTORY - DESCRIPTION OF WELL & LEASE
CONSERVATION DIVISION
WICHITA, KS

Operator: License # 32309
Name: Presco Western, LLC
Address 5665 FLATIRON PARKWAY
City/State/Zip BOULDER CO 80301
Purchaser: High Sierra Crude (oil)/BP (gas)
Operator Contact Person: Randy M. Verret
Phone (303) 305-1163
Contractor: Name: H2 Drilling, LLC
License: 33793
Wellsite Geologist: N/A

API NO. 15- 081-21777-0000
County Haskell

SE - SE - NW - NW Sec. 8 Twp. 30 S. R. 32 E W
1,280 Feet from S(circle one) Line of Section
1,272 Feet from E(circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW

Lease Name Redd Well # 5-D8-30-32

Field Name East Lemon

Producing Formation Lansing

Elevation: Ground 2,914' Kelley Bushing 2,925

Total Depth 5,680' Plug Back Total Depth 4,980'

Amount of Surface Pipe Set and Cemented at 1,854 Feet

Multiple Stage Cementing Collar Used? Yes 3, No

If yes, show depth set 3,066 Feet

If Alternate II completion, cement circulated from _____
feet depth to 11-1-70-7/2/08 _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)

Chloride content 1,800 ppm Fluid volume 4,000 bbls

Dewatering method used Air Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name _____

Lease Name _____ License No. _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ E W

County _____ Docket No. _____

Designate Type of Completion

New Well Re-Entry Workover

Oil SWD SIOW Temp. Abd.

Gas ENHR SIGW

Dry Other (Core, WSW, Expl., Cathodic, etc.)

If Workover/Reentry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date _____ Original Total Depth _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back Plug Back Total Depth _____

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr?) Docket No. _____

1/20/2008 1/29/2008

Spud Date or Date Reached TD Completion Date or Recompletion Date

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature [Signature]

Title Notary Public Date 6/11/2008

Subscribed and sworn to before me this 11th day of June

20 08 Notary Public [Signature]

My Commission Expires 02/12/2011

KCC Office Use ONLY

Letter of Confidentiality Attached

If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

Operator Name Presco Western, LLC

Lease Name Redd

Well # 5-D8-30-32

Sec. 8 Twp. 30 S.R. 32 East West

County Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets.) Yes No
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run (Submit Copy.) Yes No

Name	Formation (Top), Depth and Datums		<input type="checkbox"/> Sample
	Top	Datum	
Lansing	4,198'	-1,273'	
Swope	4,687'	-1,762'	
Marmaton	4,845'	-1,920'	
Morrow	5,305'	-2,380'	
St. Louis	5,583'	-2,658'	

List All E.Logs Run:
 Spectral Density Dual Spaced Neutron Log, Array
 Sonic Log, MicroLog

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24.0	1,855'	Lite/CL C	600/150	6%Gel/3%OC/1/4Flo
Production	7-7/8"	4-1/2"	10.5	5,085'	ASC	125	10%salt/2%Gel

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
Perforate				
Protect Casing				
Plug Back TD				
Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4,872 - 4,879' Marmaton	700G HCL/298 4%KCL Flush	
	4,688 - 4,696' Marmaton	Squeeze 50 SKS cement	

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2-3/8"	4,915'	N/A	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr. Not Producing Yet
 Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	N/A	N/A	N/A	N/A	

Disposition of Gas: METHOD OF COMPLETION Production Interval
 Vented Sold Used on Lease Open Hole Perforation Dually Comp. Commingled
 (If vented, submit ACO-18.) Other (Specify)

ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: 26759
LIBERTY KS

DATE <u>1-22-08</u>	SEC <u>8</u>	TWP. <u>30S</u>	RANGE <u>32W</u>	CALLED OUT	ON LOCATION	JOB START <u>11:00 AM</u>	JOB FINISH <u>12:30 PM</u>
LEASE <u>REDD</u>	WELL # <u>5-D9-30-32</u>	LOCATION <u>SUBLETTE 1E 15 NE</u>	COUNTY <u>HASKELL</u>		STATE <u>KS</u>		
OLD OR <input checked="" type="radio"/> NEW (Circle one)			<u>SINDO</u>				

CONTRACTOR H. J. # 1

TYPE OF JOB 8 5/8 SURFACE

HOLE SIZE 12 1/4 T.D. 1855

CASING SIZE 8 5/8 DEPTH 1854'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 25.5'

CEMENT LEFT IN CSG. 25.5'

PERFS.

DISPLACEMENT 116.3

EQUIPMENT

OWNER SAME

CEMENT AMOUNT ORDERED 600 LITE 65/35 6% GEL

3 1/2" SL 1/4" # FLOSEAL

150 "C" 3 1/2" SL

COMMON <u>C-150</u>	@ <u>17.35</u>	<u>2602.50</u>
POZMIX	@	
GEL	@	
CHLORIDE <u>36 SK</u>	@ <u>52.45</u>	<u>1888.20</u>
ASC	@	
<u>LITE 600 SK</u>	@ <u>13.35</u>	<u>8010.00</u>
<u>150 LB FLOSEAL</u>	@ <u>225.48</u>	<u>3375.00</u>
HANDLING <u>812</u>	@ <u>2.15</u>	<u>1745.00</u>
MILEAGE <u>.09 SK/mi</u>	@	<u>2191.40</u>
		TOTAL <u>16776.40</u>

PUMP TRUCK CEMENTER BOB ABEL

417 HELPER GABE

BULK TRUCK # 456/239 DRIVER DON

BULK TRUCK # 458/1 DRIVER LALO

REMARKS:

BREAK CIRC

MIX 600 SK LITE @ 12.5

MIX 150 SK 'C' @ 14.2

DRUG PLUG + DISP

LAND PLUG @ 100 PSI

FLOAT HELD

CIRC CUT TO SURFACE

SERVICE

DEPTH OF JOB <u>18'</u>	
PUMP TRUCK CHARGE	<u>1812.00</u>
EXTRA FOOTAGE @	
MILEAGE <u>30</u> @ <u>7.00</u>	<u>210.00</u>
MANIFOLD + HEAD @	<u>113.00</u>

CHARGE TO: PRESCO WESTERN

STREET _____

CITY _____ STATE _____

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 12 2008

To Allied Cementing Co., Inc. CONSERVATION DIVISION
WICHITA, KS
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

<u>1-5-W PLUG</u>	@ <u>113.00</u>	<u>113.00</u>
<u>1- GUIDE SHOE</u>	@ <u>282.00</u>	<u>282.00</u>
<u>1-SS ROOT COLLAR</u>	@ <u>675.00</u>	<u>675.00</u>
<u>10 CENTRACILERS</u>	@ <u>62.00</u>	<u>620.00</u>
<u>1 C/W BASKET</u>	@ <u>245.00</u>	<u>245.00</u>
<u>1 FLOREAD LOCK</u>	@ <u>34.00</u>	<u>34.00</u>
		TOTAL <u>1972.00</u>

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

M. D. K. Koveland
PRINTED NAME

