

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 097-20477 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date 6/26/78

Well Operator: TGT Petroleum Corp. KCC License #: 5118
(Owner / Company Name) (Operator's)

Address: 7570 W. 21st-Bldg. 1010-D City: Wichita

State: Ks. Zip Code: 67205 Contact Phone: (316) 773 - 2266

Lease: Pyle "A" Well #: 1 Sec. 2 Twp. 28 S. R. 19 East West

C E/2 SE Spot Location / QQQQ County: Kiowa

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 462' Cemented with: 325 Sacks

Production Casing Size: 5 1/2" Set at: 5049' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs. 4892'-4902' & 4543'-45'

Elevation: 2302 (G.L. / K.B.) T.D.: 5050 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per instructions of KCC representative.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 01 2008

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission, **WICHITA, KS**

List Name of Company Representative authorized to be in charge of plugging operations: _____

B. Lynn Herrington Phone: (316) 773 - 2266

Address: 7570 W. 21st-Bldg. 1010-D City / State: Wichita, Ks. 67205

Plugging Contractor: TGT Petroleum Corp. KCC License #: 5118
(Company Name) (Contractor's)

Address: 7570 W. 21st-Bldg. 1010-D Phone: (316) 773 - 2266

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/25/08 Authorized Operator / Agent: B. Lynn Herrington (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 1
PT

CONTRACTOR'S WELL LOG

OPERATOR: TGT Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Pyle "A" #1
 LOCATION: C NE SW Section 2-28S-19W
 Kiowa County, Kansas
 SPUD DATE: June 25, 1978
 COMPLETION DATE: July 11, 1978

0	302	Sand & shale
302	462	Shale
462	793	Shale & lime
793	1358	Shale
1358	3145	Shale & lime
3145	3299	Lime & shale
3299	3607	Shale & lime
3607	4340	Lime & shale
4340	4429	Shale & lime
4429	4779	Lime & shale
4779	4845	Lime
4845	4850	Shale & lime
4850	4892	Lime & chert
4892	4942	Chert
4942	5050	Lime, shale & chert
	5050	Rotary Total Depth

Spud hole at 8:30 p.m., June 25, 1978. Drilled 462' of 12½" hole. Ran 11 joints of 8-5/8" - 28# surface casing. Set at 462' with 175 sacks of lite, 3% CaCl, 2% gel, followed by 150 sacks of Class A, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 5:00 a.m., June 26, 1978.

T.D. 5050'. Ran 134 joints of 5½" - 14# 8rd thd steel casing. Set 1' off bottom at 5049' with 50 sacks of Halliburton lite, followed with 200 sacks of 50/50 posmix, 10% salt. Job complete at 12:20 p.m., July 11, 1978.

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Pyle "A" #1, C-NE-SW Section 2-28S-19W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 14th day of July, 1978.

Sandra Richman
 Sandra Richman, Notary Public



RECORDED
 JUL 14 1978
 114



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

TGT PETROLEUM CORPORATION
7570 W 21ST ST N STE1010D
PO BOX 75097
WICHITA, KS 67205-1764

December 04, 2008

Re: PYLE #1-A
API 15-097-20477-00-00
2-28S-19W, 1320 FSL 660 FEL
KIOWA COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after June 2, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888