

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-155-20210-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date 2/27/73

Well Operator: TGT Petroleum Corp. KCC License #: 5118
(Owner / Company Name) (Operator's)

Address: 7570 W. 21st-Bldg. 1010-D City: Wichita

State: Ks. Zip Code: 67205 Contact Phone: (316) 773-2266

Lease: Sabin "A" Well #: 2 Sec. 22 Twp. 23 S. R. 4 East West

ne sw nw se Spot Location / QQQQ County: Reno

840 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

580 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 640' Cemented with: 100 Sacks

Production Casing Size: 5 1/2" Set at: 3347' Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs. 3334'-38'

Elevation: 1471' (G.L. / K.B.) T.D.: 3355' P.B.T.D.: 3340' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As directed by KCC representative.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 01 2008

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

B. Lynn Herrington Phone: (316) 773-2266

Address: 7570 W. 21st-Bldg. 1010-D City / State: Wichita, Ks. 67205

Plugging Contractor: TGT Petroleum Corp. KCC License #: 5118
(Company Name) (Contractor's)

Address: 7570 W. 21st-Bldg. 1010-D Phone: (316) 773-2266
Wichita, Ks. 67205

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/25/08 Authorized Operator / Agent: B. Lynn Herrington (Signature)

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC Pkt
see
spot
research

Pkt
Dist 2



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

March 8, 1973

COMPANY: TGT PETROLEUM CORPORATION
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: SABIN # "A" 2
 LOCATION: C S/2 NW SE, Sec. 22-23-4W,
 Reno County, Kansas
 COMMENCED: February 26, 1973
 COMPLETED: March 8, 1973
 ELEVATION:

| | | | |
|------|----|------|--------------|
| 0 | to | 40 | Clay |
| 40 | to | 210 | Sand |
| 210 | to | 237 | Blue Shale |
| 237 | to | 280 | Lime |
| 280 | to | 720 | Shale & Lime |
| 720 | to | 1350 | Lime & Shale |
| 1350 | to | 1790 | Shale & Lime |
| 1790 | to | 2050 | Lime & Shale |
| 2050 | to | 2260 | Lime |
| 2260 | to | 2565 | Lime & Shale |
| 2565 | to | 3000 | Lime |
| 3000 | to | 3095 | Lime & Shale |
| 3095 | to | 3295 | Shale & Lime |
| 3295 | to | 3355 | Mississippi |
| | | 3355 | T. D. |


 Cut 17 1/4 inch hole to 237 ft. and run 239 ft. of 13 inch surface pipe, cemented with 250 sacks of cement at 237 ft., plug down at 4:00 P. M., February 27, 1973. Lost circulation at 720ft. Run 642.10 ft. of 8 5/8 inch surface pipe, cemented at 640 with 100 sacks of cement. Plug down at 11:15 P. M., March 1, 1973. Cut 7 7/8 inch hole to 3355 ft. and run 3358 ft. of used 5 1/2 inch casing, cemented at 3347 ft., 8 ft. off bottom with 75 sacks of cement. Plug down at 5:15 A. M., March 8, 1973.

TOPS: MISSISSIPPI - 3295' OSAGE - 3347'


Measurements taken from K. B.

CERTIFICATE


I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your SABIN "a" #2, located on the C S/2 NW SE, Sec. 22-23-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 8 day of March, 1973.


 Johnnie L. Schmidt - Notary Public

My Commission Expires: June 27, 1973.



REC'D
 MARCH 11 1973



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

TGT PETROLEUM CORPORATION
7570 W 21ST ST N STE1010D
PO BOX 75097
WICHITA, KS 67205-1764

December 04, 2008

Re: SABIN A #2
API 15-155-20210-00-00
22-23S-4W, 840 FNL 580 FWL
RENO COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after June 2, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000