

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-193-20,522-06-00

LEASE NAME Robben

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-10

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 10 TWP. 10 SRGE. 31 (E) or (W)

COUNTY Thomas

LEASE OPERATOR Brito Oil Co., Inc.

ADDRESS 200 E. First, Suite 208, Wichita, KS 67202

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well D&A

Date Well Completed 7-13-90

Plugging Commenced 7-13-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-14-90

The plugging proposal was approved on 7-13-90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	250	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Filled hole w/heavy mud. Set 1st plug from 2250 to 2150 w/25 sx; 2nd plug from 1650' to 1250' w/100 sx; 3rd plug from 300' to 140' w/40 sx; 4th plug from 40' to surface w/10 sx, 15 sx in rathole. All cement 60/40 pozmix 3% cc, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Co., Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Agent (~~Employer~~ or ~~Operator~~) or Operator of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202



WITNESSED TO before me this 19th day of July, 1990

Susan M. Williams
Notary Public

My Comm. Expires: 8/15/92

15-193-20522-00-00

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

Brito Oil Company, Inc.
200 E. First, Suite 208
Wichita, KS 67202

Robben #1-10
NE NE NW
Sec. 10-10S-31W
Thomas County, Kansas

8 5/8" casing set at 250' w/160 sx.
Contractor: Abercrombie Drilling, Inc.

CONTRACTOR'S WELL LOG

7-7-90	0 - 252	Sand & Shale
	252 - 303	Shale
	303 - 1468	Sand & Shale
7-8-90	1468 - 1890	Shale & Sand
	1890 - 2229	Shale
	2229 - 2532	Shale & Lime
	2532 - 2566	Anhydrite
	2566 - 2718	Shale & Lime
7-9-90	2718 - 2980	Shale & Lime
	2980 - 3460	Shale
7-10-90	3460 - 3975	Shale & Lime
7-11-90	3975 - 4085	Shale & Lime
	4085 - 4285	Lime
7-12-90	4285 - 4490	Lime
7-13-90	4490 - 4570	Shale & Lime
	4570 - 4650	Lime
	4650	Rotary total depth

RECEIVED
STATE AND COUNTY OF KANSAS

JUL 20 1990

CONSERVATION DIVISION
Wichita, Kansas