

LEASE NAME Robben

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 9 TWP. 10S RGE. 31W (E or W)

COUNTY Thomas

Date Well Completed         

Plugging Commenced         

Plugging Completed 8-25-94

TYPE OR PRINT  
 NOTICE: Fill out completoly  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR National Petroleum Reserves, Inc.

ADDRESS 250 N. Rock Rd #340 Wichita, Kansas 67206

PHONE# (316) 681-3515 OPERATORS LICENSE NO. 9482

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filled?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	321'	none
				4 1/2"	4685'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
 Pumped six sacks down backside, pumped 210 sacks down 4 1/2" 600# pressure 60/40 poz.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Petroleum Reserves, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) of (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated in the above statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 1 day of September, 19 94

Irene Herzberg  
 Notary Public

My Commission Expires: 

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 02 1994  
 REGISTRATION DIVISION  
 WICHITA, KANSAS

NOV

NOV 17

ORIGINAL

EMPHASIS OIL OPERATIONS

CONFIDENTIAL

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: National Petroleum Reserves, Inc.  
250 N. Rock Rd., Suite 340  
Wichita, KS 67206

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Robben WELL #1

LOCATION: C S/2 SW SW  
Section 9-10S-31W  
Thomas County, Kansas

LOGGERS TOTAL DEPTH: 4690'

ROTARY TOTAL DEPTH: 4690'

ELEVATION: 3026' K.B.

COMMENCED: 7/28/91

COMPLETED: 8/13/91

CASING: 8-5/8" @ 321' w/200 sks cement  
4-1/2" @ 4689' w/185 sks cement (Top Stage)  
w/425 sks cement (Bottom Stage)

STATUS: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Anhydrite	2601'	Marmaton	4372'
Shale	2638'	Myrick Station	4490'
Heebner	4031'	Johnston	4585'
Toronto	4058'	Mississippi	4624'
Lansing-Kansas City	4076'	R.T.D. STATION	4690'
Base Kansas City	4344'		

RECEIVED  
COMMISSION

NOV 25 1991

DIVISION  
WICHITA, KANSAS

STATE OF KANSAS )  
) ss  
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

*Kyle B. Branum*  
Kyle B. Branum

Subscribed and sworn to before me on August 14, 1991.

My commission expires: February 6, 1992.

GLEND A. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

*Glenda R. Tiffin*  
Glenda R. Tiffin, Notary Public