

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Haverkamp
WELL NUMBER #1
3630' F N of SE
SPOT LOCATION 2610' F W Line
SEC. 14 TWP. 10 RGE. 31 (K) or (W)
COUNTY Thomas
Date Well Completed 8-10-85
Plugging Commenced 8-11-85
Plugging Completed 8-11-85

LEASE OPERATOR American Warrior, Inc.
ADDRESS Hwy. 50 West, P.O. Box 399, Garden City, KS
67846

PHONE # (316) 275-7461 OPERATORS LICENSE NO. 4058

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? _____

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing formation None Depth to top None bottom None T.D. 4620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Pipe		0	300'	8-5/8		
Cement	200 sacks of common	3% CC	& 2%	gel		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from 40 feet to 2400 feet each set. 1st Plug set @ 2400' - 20 sacks; 2nd Plug set @ 1600' - 100 sacks; 3rd Plug set @ 400' - 40 sacks; 4th Plug set @ 40' - 10 sacks. Rat hole plugged with 10 sacks. Total sacks of cement 180 sacks of 60/40 pos & 6% CC & 3% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J. Titan Service Co. License No. _____
Address Oakley, KS


STATE OF KANSAS COUNTY OF ELLIS, ss.

Isadore P. Kisner (employee of operator) or
~~operator~~ of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Isadore P. Kisner

(Address) 3000 Broadway Ave., Suite C
Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 15 day of August, 1985



Rosalind A. King
Notary Public
STATE CORPORATION COMMISSION

My Commission expires: May 28, 1989

FEB 20 1986