

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-193-20,584-00-00

LEASE NAME Beckman "A" #2

WELL NUMBER 2

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 14 TWP. 10 SRGE. 31 (E) or (W)

COUNTY Thomas

Date Well Completed 12/26/91

Plugging Commenced 12/26/91

Plugging Completed 12/26/91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR N-B Company, Inc.

ADDRESS P. O. Box 506, Russell, KS 67665-0506

PHONE#(913) -689-4814 OPERATORS LICENSE NO. 6111

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-26-91 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4551'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	253'	-0-

DEC 30 1991

REGISTRATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4551'-1620' 10 sks cement in rathole

25 sks cement @ 1620' 15 sks cement in mouse#

100 sks cement @ 1300' hole

40 sks cement @ 300'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: N-B Company, Inc.


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506



SUBSCRIBED AND SWORN TO before me this 27th day of December, 1991


[Signature]  
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

Form CP-4  
Revised 05-88

Subscribed and sworn to before me on December 27, 1991.

My commission expires: February 6, 1992.



[Signature]  
Glenda R. Tiffin, Notary Public

15-193-20584-00-00

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1991

EMPHASIS OIL OPERATIONS  
P. O. BOX 506  
RUSSELL, KS 67665

SERVATION DEPARTMENT  
WICHITA...

DRILLERS LOG

OPERATOR: N-B Company, Inc.  
P. O. Box 506  
Russell, Kansas 67665-0506

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Beckman 'A' WELL #2

LOCATION: C SW NE  
Section 14-10S-31W  
Thomas County, Kansas

LOGGERS TOTAL DEPTH: 4551'

ROTARY TOTAL DEPTH: 4551'

COMMENCED: 12/16/91

CASING: 8-5/8" @ 253' w/160 sks cement

ELEVATION: 2912' K.B.

COMPLETED: 12/26/91

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	60'	Toronto	3782'
Shale	2305'	Lansing-Kansas City	3955'
Anhydrite	2490'	Pawnee	4335'
Red Bed	2523'	Mississippi	4515'
Shale & Lime	3410'	R.T.D.	4551'
Lime & Shale	3600'		


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on December 27, 1991.

My commission expires: February 6, 1992.

 **GLEND A. R. TIFFIN**  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

  
\_\_\_\_\_  
Glenda R. Tiffin, Notary Public