

LEASE NAME Haverkamp

WELL NUMBER 1

2970 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 14 TWP. 10S RGE. 31 XXXX(W)

COUNTY Thomas

Date Well Completed 12-31-88

Plugging Commenced 1-01-89

Plugging Completed 1-01-89

LEASE OPERATOR Blackhawk Exploration, Inc.

ADDRESS 200 E. First, Suite LL 100, Wichita, KS 67202

PHONE#(316) 265-6431 OPERATORS LICENSE NO. 4480

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-01-89 (date)

by State Plugger, Ed Schumacher (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	361'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Circulate heavy mud in hole. 1st plug from 2670' to 2590' w/20 sx. 2nd plug from 1680' to 1280' w/100 sx. 3rd plug from 410' to 250' w/40 sx. 4th plug from 40' to surface with wiper plug w/10 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Blackhawk Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1989

Janet A. Stuck  
Notary Public 1-17-89

Commission Expires: 12-29-90

