

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2028
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-193-20424-00-00

LEASE NAME Huelsman H

WELL NUMBER 1

1650 Ft. from ^N Section Line

2200 Ft. from E Section Line

SEC. 15 TWP. 10S RGE. 31 (E) or (W)

COUNTY Thomas

Date Well Completed _____

Plugging Commenced 8-19-03

Plugging Completed 8-20-03

AUG 29 2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation ANH + LKC Depth to Top _____ Bottom _____ T.O. 4734

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	323	8 5/8		
	Prod.	0	4734	4 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Rig up POE Well Ser. TOH 147. Remove mud anchor + T.H. 145. Shut Down. Rig up Allied + bfg. @ 4600' Pump 100 SX 60/40 1090 w/500 # hulls. Pull 73 its + bfg @ 2200' Circ cement to surf. w/110 SX 60/40 1090 No hulls TOH w/bfg. Tie onto 8 5/8 pump 55X down annulus. psi ~~800~~ 800 # + S.I. Tie onto 4 1/2 csg. mixed 25 SX psi to 800 # + S.I.
Witnessed by D. Dipman KCC Hays

Name of Plugging Contractor Poe Well Service License No. 3152

Address P.O. Box 115 Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mark Leiker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Mark Leiker

(Address) P.O. Box 723, Hays, KS

SUBSCRIBED AND SWORN TO before me this 25th day of August, 03

Marion Sue Vance
Notary Public

My Commission Expires: 4-30-06



KCC Form 1 Revised 05-88

AUG 29 2003

HAYS, KS