

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,570-00-00

LEASE NAME Beckman 'A' #1

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR N-B Company, Inc.

SEC. 14 TWP. 10S RGE. 31 (E/W or W)

ADDRESS P. O. Box 506, Russell, KS 67665-0506

COUNTY Thomas

PHONE# (913) -483-5345 OPERATORS LICENSE NO. 6111

Date Well Completed 10/1/91

Character of Well _____

Plugging Commenced 10/1/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/1/91

The plugging proposal was approved on 10-1-91 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	257'	-0-

OCT 14 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4630'-2570' 10 sks cement @ 40'
 25 sks cement @ 2570' 15 sks in rathole
 100 sks cement @ 1670' 10 sks in mousehole
 40 sks cement @ 260'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: N-B Company, Inc.


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1991



Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

15-193-20570-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1991

EMPHASIS OIL OPERATIONS

... DIVISION
Wichita, Kansas

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, KS 67665-0506

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Beckman 'A' WELL #1

LOCATION: E/2 SE NW
Section 14-10S-31W
Thomas County, Kansas

LOGGERS TOTAL DEPTH: 4631'

ROTARY TOTAL DEPTH: 4630'

COMMENCED: 9/24/91

CASING: 8-5/8" @ 257' w/160 sks cement

ELEVATION: 2970'

COMPLETED: 10/1/91

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand and Shale	262'	Shale and Lime	3705'
Stone Coral	2537'	Heebner	3980'
Anhydrite	2556'	Toronto	4020'
Sand and Shale	2570'	Lansing-Kansas City	4294'
Shales	3093'	Mississippi	4600'


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on October 1, 1991.

My commission expires: April 12, 1991.


Katherine Bray, Notary Public

