

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 157193-20,579-0000

LEASE NAME Baalman "B"

WELL NUMBER 1

4190
990 Ft. from S Section Line

1,650 Ft. from E Section Line

SEC. 19 TWP. 10 SRGE. 31 ~~EX~~ or (W)

COUNTY Thomas

Date Well Completed 11-27-91

Plugging Commenced 11-27-91

Plugging Completed 11-27-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, KS. 67665

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-27-91 (date)

by Ed Schumacker (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	302'	Cmtd. w/225 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Spot 25 sax cement @2,590' thru drill pipe. Spot 100 sax cement @19720 thru drill pipe. Spot 40 sax cement @350' thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Cement is 60-40 Pozmix w/6% jel and 2 sax cello-flake. Plug down at 2:30 PM
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 1645655

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~XXXXXX~~ or ~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 91

Ruth Phillips

Notary Public



DEC 17 1991

CONSERVATION DIVISION My Commission Expires: _____
Wichita, Kansas



Shields


15-193-20579-0000

Russell, Kansas

WELL LOG

Operator: John O. Farmer, Inc.
 Well: Baalman "B" #1
 Commenced: November 21, 1991
 Completed: November 27, 1991
 Contractor: Shields Drilling Co.

Well Description: SE NW NE
 Sec. 19-10S-31W
 Thomas County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	302'	Cmtd. w/225 sax

Elevation: 3,025' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	2,440'	
Shale & lime streaks	2,570'	
Anhydrite	2,605'	
Shale & lime streaks	2,701'	
Shale & lime	4,127'	
Lime	4,340'	RTD

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1991

REGISTRATION DIVISION
Wichita, Kansas

Notes