

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

212 N. Market

Thomas

County. Sec. 23 Twp. 10S Rge. (E) 31(W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Johnie S. Carter
Lease Name Stephen Broeckelman Well No. 1
Office Address P. O. Box 194, Fairfield, Illinois
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 17 1958
Application for plugging filed March 17 1958
Application for plugging approved March 17 1958
Plugging commenced March 18 1958
Plugging completed March 18 1958
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4876 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	No show			8-5/8"	212'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 4876' to 400'

Cement from 400' to 363' - 25 sacks of cement

Mud from 363' to 200'

Cement from 200' to 178' - 15 sacks of cement

Mud from 178' to 40'

Cement from 40' to 2' below Ground Level

RECEIVED
STATE CORPORATION COMMISSION
3-28-58
MAR 29 1958
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Johnie S. Carter License No. 346, Docket No. 52,
Address 306 C.A. Johnson Bldg, Denver, Colo. & P.O. Box 194, Fairfield, Illinois 848-C, C-5150

STATE OF ILLINOIS, COUNTY OF WAYNE, ss.
Harry J. Phillips

(employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry J. Phillips, Tool Pusher
For: JOHNIE S. CARTER DRLG. CONTR.
P. O. Box 194, Fairfield, Ill.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1958

My commission expires March 22, 1959

Evelyn N. Mitchell
Commissioned & residing in _____
Richland County, acting in Wayne Co., Ill.



PLUGGING
FILE NO. 23-10R.311
BOOK NO. 9.0 LINE 42

JOHNIE S. CARTER DRILLING CONTRACTOR
P. O. BOX 194
Fairfield, Illinois

LOG of BROCKELMAN #1 Thomas County, Kansas

COMPANY: Johnie S. Carter
CONTRACTOR: Johnie S. Carter
LEASE: Brockelman #1
LOCATION: NE NE NE
Sec 23-10S-31W
Thomas County, Kansas

ELEVATION: 2944 G.L.
CASING RECORD: Set 212"
8-5/8" Surface
Cemented w/200 sacks
H.A.5 cement

COMMENCED: January 7, 1958
COMPLETED: March 17, 1958

TOTAL DEPTH: 4876'

INITIAL PRODUCTION: D & A

Date	From	To	Formation
1-6-58	0	219	Clay, shale
1-7-58	219	665	Shale
1-8-58	665	800	Shale, shells
	800	950	Lime
	950	1340	Shale, Shells
	1340	1405	Sand
Well shut down 1-8-58 to 2-21-58			
2-22-58	1405	1530	Sand, shale
	1530	1919	Sand, shale streaks
	1919	2150	Sand, shale
	2150	2190	Shale
	2190	2225	Gyp
	2225	2388	Shale
2-23-58	2388	2515	Shale
	2515	2580	Lime, shale
	2580	2700	Shale, shells
2-24-58	2700	2815	Shale, Lime
	2815	3008	Shale, Lime streaks
	3008	3055	Lime, Shale
2-25-58	3055	3120	Lime, shale
	3120	3268	Shale, lime streaks
	3268	3273	Lime
2-26-58	3273	3407	Lime
2-27-58	3407	3527	Lime
2-28-58	3527	3532	Shale
	3532	3559	Lime, shale
3-1-58	3559	3640	Lime
3-2-58	3640	3810	Lime
3-3-58	3810	3887	Lime
	3887	3982	Lime, shale streaks
	3982	3992	Lime, shale
	3992	4030	Lime
3-4-58	4030	4054	Lime
3-5-58	4054	4206	Lime
3-6-58	4206	4215	Lime
	4215	4285	Lime, shale
3-7-58	4285	4290	Lime
	4290	4355	Lime, shale
3-8-58	4355	4380	Lime, shale streaks
	4380	4422	Lime, shale
	4422	4452	Shale, lime streaks
3-9-58	4452	4515	Lime, shale
	4515	4550	Lime
3-10-58	4550	4586	Lime
	4586	4619	Shaley lime
	4619	4639	Lime
3-11-58	4639	4734	Lime

RECEIVED
CONSERVATION COMMISSION
MAR 28 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 23T 10 R 31W
BOOK PAGE 90 LINE 72

JOHNIE S. CARTER DRILLING CONTRACTOR
P. O. Box 194
Fairfield, Illinois

Log of Brockelman #1, Thomas County, Kansas

3-12-58	4734	4751	Line, chert
	4751	4786	Line
	4786	4820	Line, shale
3-13-58	4820	4876	Line


Lost circulation in Arbuckle at 4876'. Unable to regain circulation, so with Phillips O.K. well was plugged at T.D. of 4876'. Lost circulation at first porosity in Arbuckle Formation - top of formation was 4859'.

I hereby certify the above and foregoing to be a true and correct copy of the Log on the Brockelman #1, located in the NE NE NE of Section 23, Township 10 South, Range 31 West, Thomas County, Kansas.

Harry J. Phillips
Tool Pusher
For: JOHNIE S. CARTER DRLG. CONTR.

Subscribed and sworn to before me this 24th day of March, 1958.

Lucy N. Mitchell
Notary Public, commissioned & residing in Richland County, Acting in Wayne County, Illinois



My Commission Expires: March 22, 1959

PLUGGING
FILE: SEC. 23 T. 10 R. 31 W
BOOK PAGE 90 LINE 72

RECEIVED
STATE CONSERVATION COMMISSION
MAR 28 1958
CONSERVATION DIVISION
Wichita, Kansas