

STATE OF KANSAS
STATE CORPORATION COMMISSION
300 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,467-0000

LEASE NAME Miller Trust

WELL NUMBER #1

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 32 TWP. 10 RGE. 31 ~~XX~~ or (W)

COUNTY Thomas

Date Well Completed 10-19-88

Plugging Commenced 10-19-88

Plugging Completed 10-19-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR National Petroleum Reserves, Inc.

ADDRESS 260 N. Rock Rd. Ste 215 Wichita, KS 67206

PHONE (316) 681-3515 OPERATORS LICENSE NO. 9482

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-18-88 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom 4640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1988
10-27-88
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 2550' w/25 sacks 60/40 pozmix 6% gel thru drill pipe
Next Plug: @ 1700' w/100 sacks " " " " & 1 sack Flo Seal thru drill pipe
Next Plug: @ 340' w/40 " " " " thru drill pipe
Top Plug: @ 40' w/ 15 sacks cement, 15 sacks in Rat Hole
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


Ervin Neighbors (Employee of Operator) or (~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors
(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 26 day of October, 1988

Dorothy M Hague
Notary Public

My Commission Expires: _____



15-193-20467-0000

DRILLER'S WELL LOG

DATE COMMENCED: October 13, 1988

DATE COMPLETED: October 19, 1988

National Petroleum Reserves, Inc.
MILLER TRUST #1
NE SW NW
Sec. 32, T10S, R31W
Thomas County, KS

- 0 - 1207' Sand, Clay, Shale
- 1207 - 2054' Shale, Lime
- 2054 - 2460' Lime, Shale, Red Bed
- 2460 - 2536' Shale, Lime
- 2536 - 2565' Anhydrite
- 2565 - 3147' Lime, Shales
- 3147 - 3450' Lime, Shales, Red Bed
- 3450 - 4130' Shale, Lime
- 4130 - 4312' Lime
- 4312 - 4640' Lime & Shale
- 4640' RTD

Elevation: 2996 K.B.

Surface Pipe: Set 8 5/8",
20# pipe at 305' w/180
sacks 60/40 Pozmix, 2% gel,
2% C.C.

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1988

CONSERVATION DIVISION
Wichita, Kansas


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 26 day of October, 1988.



Dorothy M Hague
Notary Public