

6 031185

10-27

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,847 - 00-00

NW SE SW SEC. 17, T 10 S, R 26 W/E

990 feet from S section line

3630 feet from E section line

Lease Name Coburn Well # 1-17

County Sheridan 145.93

Well Total Depth 4490 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 256

TECHNICIAN'S PLUGGING REPORT

Operator License # 4036

Operator: Pittman and Assoc. Inc.

Name & Address 5921 S. Middlefield Rd #200

Littleton, Colorado 80245

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_

Address Rbssell, Ks.

Company to plug at: Hour: PM Day: 27 Month: Oct Year: 19 88

Plugging proposal received from Clint Base

(company name) Pittman and Assoc Inc. (phone) \_\_\_\_\_

were: 8 5/8" set at 256' w/160 sks cwc 4 1/2" set at 4131' w/125 sks.

Perf 3900' - 3904' Stage collar at 2288' cwc w/600 sks. Order 160 sks 65/35 Poz 10%

Gel 2% DiGel 500# Hulls. Allied Cement Co. Fritzier Water Truck. Tubing pulled and

hole open to perfs. Completed in 1986.

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 27 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/160 sks Cement Blend w/500# Hulls mixed in

to max Psi 1100#. Close in Psi 800#. Test backside w/0 sks to max psi 300#. Plug

complete. Cement to be thicker across perfs, Dakota and surface perfs. 23 gal/sk

spacers 11 gal/sk plugs.

RECEIVED STATE CORPORATION COMMISSION

12-29-88

DEC 29 1988

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

D

DATE 1-6-89

INV. NO. 23513