

6 030944

9-1-87

179-20,899 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

W/2 W/2 NW, SEC. 17, T 10 S, R 26 (W/2)

3960 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267

Lease Name Johnson Well # 1 - 17

Operator: K and E Petroleum Inc.
Name & Address: 100 S. Main Suite 300
Wichita, Kansas 67202

County Sheridan 134.55

Well Total Depth 4140 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 54222

Address Wichita, Kansas

Company to plug at: Hour: PM Day: 1 Month: Sept Year: 19 87

Plugging proposal received from Harold Maley

(company name) Abercrombie (phone) _____

were: 8 5/8" set at 277' w/190 sks cwc. Circulate hole with no less than

36 vis mud and with no loss or gain of hole fluids. Displace cement plugs with

drill pipe and balance all plugs with mud. Order 190 sks 60/40 Pozmix 6% Gel 3% Ca

Cl Cement Blend and 8 5/8" wiper plug. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1:00 PM Day: 1 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT

With drill pipe displace 25 sks at 2275'

100 sks at 1300' w/ 1 sk Hulls

40 sks at 325'

10 sks at 40' w/wiper plug to Kelly depth RECEIVED

15 sks in rat hole w/pipe.

STATE CORPORATION COMMISSION

Remarks: Anyh 2266' - 96' Elevation 2629.

SEP 25 1987

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INVOICED

DATE 9-29-87

INV. NO. 18290