

8-7

4-060418

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,064-0000

C W2 NE /4 SEC. 22, 10 S, 26 W
3960 feet from S section line
1980 feet from E section line

Operator license# 5422 Lease Rhoades well # 1

Operator: Abercrombie Drilling, Inc. County Sheridan

Address: 150 N. Main Well total depth 4110 feet
Suite #801 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 228 feet

133.57

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie RTD., Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: 5:30P.M. Day: 7 Month: August Year: 93

Plugging proposal received from: Gary Fisher

Company: Abercrombie RTD., Inc. Phone: 316-262-1841

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:30P.M., Day: 7, Month: August, Year: 93

Actual plugging report:
1st. plug at 2225' w/ 25 sxs. - Anhydrite 2209' - 2249'.
2nd. plug at 1300' w/100 sxs. - Dakota 990' - 1290'.
3rd. plug at 280' w/ 40 sxs. - Surface pipe to 228'.
4th. plug at 40' w/ 10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO
Plugged through TUBING , CASING . Elevation: 2565 GL

I did[] / did not[] observe the plugging.

[Signature] AUG 20 1993

RECEIVED
STATE CORPORATION COMMISSION

DH (agent) CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3

INVOICED

DATE AUG 30 1993

INV. NO. 38495 OCT 13 1993