

6 090300

PLUGGED

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20, 863-00-00

SW 1/4 SEC. 19, T. 10 S, R. 30 W

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8000

Lease Name Beckmann Well #14-9-1

Operator: Pan Canadian Petroleum Co.

County Shelby 157.63

Name & Address Box 929

Well Total Depth 4850 feet

Denver, Colorado 80202

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Co. License Number 5418

Address Great Bend, Ks.

Company to plug at: Hour:  Day: 28 Month: April Year: 19 86

Plugging proposal received from Steve Dunbar

(company name) Allen Drilling Co. (phone)

were: Order 200 sks. 60/40 permit, 670 gal + 8 5/8  
injection plug, spot all plugs through drill pipe w/  
heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7:00 PM Day: 28 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1<sup>st</sup> plug 4730' w/ 20 sks.

2<sup>nd</sup> plug 2460' w/ 20 sks.

3<sup>rd</sup> plug 1570' w/ 100 sks. + 1 sk. Cello-Floke

4<sup>th</sup> plug 350' w/ 40 sks.

5<sup>th</sup> plug 40' solid bridge w/ 10 sks.

10 sks in rat hole

Remarks: Elevation - 2922' Anhydrite - 2458' Arbuckle - yes  
(If additional description is necessary, use BACK of this form (B.G. Eaton) 7-10-86)

INVOICED (do not observe this plugging)

DATE JUL 14 1986

INV. NO. 14361  
4-28

STATE CORPORATION COMMISSION

JUL 11 1986

CONSERVATION DIVISION

Signed Edwin A. Schumacher  
(TECHNICIAN)