

6-090484

4-27

257
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,033-00-00

SW NW NW /4 SEC. 07, 10 S, 30 W
990 feet from N section line
330 feet from W section line

Operator license# 5015

Lease Schiltz Well # 1

Operator: Hellar Drilling Company, Inc

County Sheridan

Address: 125 North Market, Suite 1422
Wichita, Kansas 67202
(316)267-2845

Well total depth 4680 feet ^{152.10}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 263 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Blue Goose Drilling Company, Inc. License# 5104

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 24 Month: April Year: 1992

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling Company, Inc phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2570 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1620 feet " 100 " Mousehole: sacks
3rd plug @ 310 feet " 40 "
4th plug @ 40 feet " wiper plug & 10 sks.

5th plug @ feet "

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00 AM, Day: 27, Month: April, Year: 1992

Actual plugging report: Hole reported plugged as above.
Order 190 sx 60/40 pozmix w/ 6% gel and 1 sx celloflake or flowcel.

Remarks: Elevation: 2971 GL, Anhydrite depth: 2550 - 2580 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: None
Plugged through drill pipe: YES
Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did[] / did not[X] observe the plugging.

Ed Schumacher
Ed Schumacher
(agent)

DATE 5-14-92

INV. NO. 35242

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1992
CONSERVATION DIVISION
Wichita, Kansas

170