

4-032123

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

12-21

API Number: 15-179-20,871-00-00

SE SW SW /4 SEC. 31, 10, 30 W  
330 feet from S section line  
4290 feet from E section line

Operator license# 4767

Lease: Beckman "P" Well # 6

Operator: Ritchie Exploration, Inc.

County: Sheridan

Address: 125 N. Market - Suite #1000  
Wichita, Kansas 67202

Well total depth 4610 <sup>149.83</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 228 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 21 Month: December Year: 1995

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone:

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 11:30 A.M. Day: 21 Month: December Year: 1995

Actual plugging report: 8 5/8" set at 228' cwc with 175 sxs. 4 1/2" set at 4604' with 200sxs. P.B.T.D. 4578'. Prod. Perf. 4156' - 4488'. D.V. set at 2555' with 490 sxs cwc. Test 8 5/8" with 20 sxs cement blend. Squeezed 4 1/2" with 250 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING Elevation: GL

I did / did not [ X ] observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
Carl Goodrow  
(agent)

DATE JAN 17 1996

JAN 10 1996  
1-10-96

Form CP-2/3

INV. NO. 44638

CONSERVATION DIVISION  
Wichita, Kansas