

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20870-00-01  
Spot: NWSESW Sec/Twnshp/Rge: 31-10S-30W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: BECKMAN P Well Number: 5  
County: SHERIDAN Total Vertical Depth: 4536 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Conductor Pipe: Size feet: 4 1/2  
Surface Casing: Size 8.625 feet: 263 w/200 sxs cmt  
Production: Size 4.5 feet: 4526 w/700 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/08/2003 9:00 AM  
Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.  
Proposal Rcvd. from: PETE EIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix and 500# hulls.  
Plug through 4 1/2" casing.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/08/2003 10:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" set at 263' w/200 sxs cement. 4 1/2" set at 4526' w/700 sxs cement.  
Perfs at 4052' and 4478'. PBTD 4500'.  
DV Tool at 2560' w/500 sxs.  
Connected to 4 1/2" production casing.  
Pumped 225 sxs with 500# hulls.  
Max. P.S.I. 500#. S.I.P. 300#.  
Topped 8 5/8" w/10 sxs cement.  
Plug complete.

RECEIVED  
JAN 14 2003  
KCC WICHITA

Remarks: LEASE FORMERLY KNOWN AS BECKMAN #5-31. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-14-03

INV NO 2003061072

JAN 09 2003


31-10-30W  
NW SE SW

DCN E. PRATT  
P.O. BOX 370 #5-31 BECKMAN  
HAYS, KS. 67601

CONTR MUREIN DRILLING CITY SHERIDAN

GEOLOGIST RANDALL KILIAN FIELD CAMPUS SIDING NE

ELV 2974 KB SPD 9/18/86 CARD ISSUED 10/30/86 IP P 80 BO & 10 BWPD  
2969 GL DRLG COMP 9/25/86 LKC 4258-4290 OA



LOG	Tops	Depth/Datum	API 15-179-20,870
ANH	2529+	445	8 5/8 " 263 / 200 SX, 4 1/2 " 4526 / 200 SX, DV TOOL AT 2560 / 500 SX NO CORES DST (1) 4040-4084 (LKC) / 30-45-30-45, 45' GIP, REC 75' SLI OIL SPTD M, SIP 1073-1032#, FP 33-58 / 67-92#, HP 2063-2048#, BHT 110° DST (2) 4083-4119 (LKC) / 30-45-30-45, REC 75' OIL, 120' GSY MCO, 180' GSY OCM, 120' SLI OCMW, SIP 1206-1183#, FP 33-166 / 183-250#, HP 2080-2038#, BHT 114° DST (3) 4147-4235 (LKC) / 30-45-30-45, REC 140' M, W / SCUM OF OIL, SIP 1189-1098#, FP 67-108 / 112-133#, HP 2197-2180#, BHT 112° DST (4) 4232-4300 (LKC) / 30-45-30-45, GTS / NT, TSTM, REC 150' OCM, 60' HOCM, 1020' FROTHY OIL (GR 39%), SIP 907-916#, FP 100-383 / 391-516#, HP 2230-2205#, BHT 114° DST (5) 4403-4536 (MARM) / 30-45-30-45, 635' GIP, REC 125'
B/ANH	2558+	416	
TOP	3759-	785	
HEEB	3984-	1010	
TOR	4003-	1029	
LANS	4022-	1048	
STARK	4238-	1264	
BKC	4295-	1321	
PAW	4424-	1450	
FT SC	4491-	1517	
CHER	4521-	1547	
CHER SD		NOT RPTD	
MISS		NOT RPTD	
RTD		4536-1562	

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)