

4-032007

10-27

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-20,539-00-00

C NW SE /4 SEC. 31, 10 S, 30 W  
1980 feet from S section line  
1980 feet from E section line

Operator license# 4767

Lease Baalman "P" well # 1

Operator: Ritchie Exploration, Inc.

County Sheridan

Address: 125 N. Market - #1000  
Wichita, Kansas 67202

Well total depth 4361 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 273 feet

14173

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: ~~Kelso Casing Pulling, Inc.~~ License# 2537  
Mike's Testing & Salvage, Inc. 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 27 Month: October Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling, Inc. Phone:

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 1:10 P.M., Day: 27, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 273' w/200 sxs. cwc. 4 1/2" set @ 4358' w/200 sxs. Prod. perfs. 4068' - 4298'. Sand back to 3992' w/4 sxs. common cement on sand with bailer. Shots 2503' - 2214' - 2008' - 1804' - 1604' - free at 1115'. Mixed and pumped 115 sxs. cement blend w/ 450# hulls to 2503' w/500# - pump pressure. Pulled to 300' cwc. with 65 sxs. Pulled casing topped off with 10 sxs. Total 190 sxs. with 500# hulls. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING X. Elevation: GL WICHITA, KANSAS

NOV 08 1994

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

DATE 11-8-94

INV. NO. 41612

INVOICED