

4-032122

01

12-21

API Number: 15-179-20,866-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE SW SW /4 SEC. 31, 10, 30 W
990 feet from S section line
4290 feet from E section line

Operator license# 4767

Lease: Beckman "P" Well # 4

Operator: Ritchie Exploration, Inc.

County: Sheridan

Address: 125 N. Market - Suite #1000
Wichita, Kansas 67202

Well total depth 4260 ^{138.45} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 21 Month: December Year: 1995

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone:

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:15 A.M. Day: 21 Month: December Year: 1995

Actual plugging report: 8 5/8" set at 264' cwc with 200 sxs. 4 1/2" set at 4613' with 200sxs. P.B.T.D. 4570'. Prod. Perf. 4282' - 4497'. D.V. set at 2536' with 500 sxs cwc. Test 8 5/8" with 15 sxs cement blend to Max. P.S.I. 500#. Held. Squeezed 4 1/2" with 225 sxs cement blend with 500# hulls mixed into Max. P.S.I. 1000#. Close in P.S.I. 800#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING. Elevation RECEIVED STATE CORPORATION COMMISSION GL

I did / did not [X] observe the plugging.

DATE JAN 17 1996

INV. NO. 44637

Handwritten initials

Signature: Carl Goodrow
JAN 10 1996 (agent)
1-10-96
Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas