

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20865-00-00
Spot: SWSESW Sec/Twnshp/Rge: 31-10S-30W
330 feet from S Section Line, 3680 feet from E Section Line
Lease/Unit Name: BECKMAN P Well Number: 3
County: SHERIDAN Total Vertical Depth: 4650 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 270 200 SX CMT
Production: Size 4.5 feet: 4650 700 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/08/2003 10:15 AM
Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 500# hulls.
Plug through 4 1/2" casing.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/08/2003 11:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" set at 270' w/200 sxs cement. 4 1/2" set at 4650' w/700 sxs cement.
Perfs at 4045' and 4583'. PBTd 4617'.
DV Tool at 2535' w/500 sxs.
Connected to 4 1/2" production casing.
Pumped 260 sxs with 500# hulls.
Max. P.S.I. 500#. S.I.P. 400#.
Topped 8 5/8" w/10 sxs cement.
Plug complete.

RECEIVED
JAN 14 2003
KCC WICHITA

Remarks: LEASE FORMERLY KNOWN AS BECKMAN 3-31. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED


Form CP-2/3

DATE 1-14-03

INV. NO. 2003061072

JAN 09 2003

DON E. PRATT
 P.O. BOX 370 #3-31 BECKMAN 31-10-30W
 HAYS, KS. 67601 50' W. C. SW SE SW
 CONTR MURFIN DRILLING CTY SHERIDAN
 GEOL _____ FIELD CAMPUS SIDING NE
 ELV 2973 KB SPD 8/26/86 CARD 10/30/86 IP P 20 BO & 10 BWPD
 2968 GL DRLG COMP 9/4/86 LKC 4166-4282 OA



LOG	Tops	Depth/Datum	API 15-179-20,865
ANH	2522+	451	8 5/8 " 270 / 200 SX, 4 1/2 " 4650 / 200 SX, DV TOOL AT 2535
TOP	3754-	781	/500 SX
HEEB	3975-	1002	NO CORES
TOR	3995-	1022	DST (1) 4033-4079 (LKC) / 30-45-30-45, REC 65' SLI OIL SPTD
LANS	4013-	1040	M, SIP 1140-1114#, FP 37-42 / 50-67#
STARK	4230-	1257	DST (2) 4078-4129 (LKC) / 30-45-30-45, 60' GIP, REC 30'
BKC	4285-	1312	CLEAN GSY OIL, 150' HOCM, 60' OCM, 180' WTR (CHL 41,000
PAW	4414-	1441	PPM), SIP 855-846#, FP 25-134 / 151-218#
FT SC	4481-	1508	DST (3) 4135-4215 (LKC) / 45-60-45-60, REC 136' SLI OIL SPTD
CHER SH	4508-	1535	GSY M, SIP 441-400#, FP 58-83 / 100-133#
CHER SD	4590-	1617	DST (4) 4233-4290 (LKC) / 30-45-30-45, 987' GIP, REC 70'
MISS	4596-	1623	CLEAN GSY OIL, 366' VHOQ GSY M, 60' OCM, SIP 857-832#, FP
RTD	4650-	1677	50-166 / 175-200#
			DST (5) 4398-4510 (PAW, FT SC) / 30-45-30-45, 318' GIP, REC
			174' SLI OC GSY M, 304' HOC GSY M, 122' OC GSY M, SIP
			1198-1147#, FP 83-316 / 308-358#

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)