

4-031962

8-18

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,937-00-00

SW SW NW /4 SEC. 32, 10 S, 30 W
2970 feet from S section line
4950 feet from E section line

Operator license# 5086

Lease Baalman well # 1-G

Operator: Pintail Petroleum, Inc.

County Sheridan

151.13

Address: 225 North Market
Suite #300
Wichita, Kansas 67202

Well total depth 4650 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 323 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: D S & W Well Service, Inc. License# 6901

Address: Claflin, Kansas

Company to plug at: Hour: P.M. Day: 18 Month: August Year: 94

Plugging proposal received from: Kevin

Company: D S & W Well Service, Inc.

Phone:

Were: Order 210 sxs. 60/40 pozmix - 10% gel - 500# hulls
Allied Cement Company.
Order 5 sxs. gel.

STATE CORPORATION COMMISSION
RECEIVED
8-24-94
AUG 24 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:00P.M., Day: 18, Month: August, Year: 94

Actual plugging report: 8 5/8" set @ 323' w/200 sxs. 4 1/2" set @ 4510'
w/150 sxs. cwc. Stage collar @ 2530' w/250 sxs. cwc. P.B.T.D. 4551'.
Prod. perfs. 4422' - 4430'. Tested 8 5/8" to Max. P.S.I. 500#. w/15 sxs.
Squeezed 4 1/2" w/50 sxs. cement blend w/200# hulls mixed in followed w/5
gel and 145 sxs. cement blend with 300# hulls mixed in to Max. P.S.I.
200#. Close in P.S.I. 200#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] did not [] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

DATE 9-6-94

INV. NO. 41105