

4- 041392

7-30

SR

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,598-00-00

E2 SE SE /4 SEC. 08 , 10 S, 31 W
710 feet from S section line
330 feet from E section line

Operator license# 9482

Lease Broeckelman well # 1

Operator: National Petroleum Res. Inc

County Thomas

Address: 250 N. Rock Road
#340
Wichita, Kansas 67206

Well total depth 4650 feet ^{151.12}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 318 feet
w/215 sx.

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Drilling License#

Address:

Company to plug at: Hour: 5:30A.M. Day: 30 Month: July Year: 92

Plugging proposal received from: Jack Fox

Company: Emphasis Drilling Phone:

Were: Order 190 sx. cement 60/40 pozmix - 6% gel. & 1/4# flocele.
Heavy mud between all plugs. Pump cement down drill pipe.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:30A.M., Day: 30, Month: July, Year: 92

Actual plugging report:
1st. plug at 2625' w/25 sx.
2nd. plug at 1730' w/100 sx.
3rd. plug at 350' w/40 sx.
4th. plug at 40' w/10 sx.
15 sx. in Rathole.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did [] / did not [X] observe the plugging.

Dennis L. Hamel

INVOICED
DATE 8-20-92
INV. NO. 35999

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1992
CONSERVATION DIVISION
WICHITA, KANSAS